



Proposal
Date: 6/11/2014
Estimate #: 5439A

Prices based upon in-stock units and good for 15 days from
above date.

111B DUNBAR AVENUE OLDSMAR, FLORIDA 34677

To: Johan Jongsma
851 Brightwaters Blvd.
St. Petersburg, Florida 33704

We are pleased to provide the following estimate for your consideration:

GENERAC

Job: Generac Generator Residential Installation

Size: 48kw – Model #QT048G Commercial Generator **Liquid Cooled 1800RPM Quiet Source**

Job to include the following:

1. Model # QT048G 48kw Commercial Generator (**Aluminum Sound Enclosure**)
2. Engineer And Build 36" Concrete Block Structure, Stucco and Painted To Match A/C Platform
3. Delivery, Set Up, and Position Generator Onto New Concrete Structure
4. Connect To Existing Natural Gas System
5. Run 5' Of Natural Gas Line To New Generator (**On Wall**)
6. 35' Electrical Line Run To New Transfer Switch (**Below Ground**)
7. 200 Amp Automatic Transfer Switch (**X2**) (**Provides Power To Entire Home**)
8. 200 Amp Service Disconnect (**X2**)
9. Electrical Hook Up And Connections
10. **Natural Gas and Electrical Permit Is Included**
11. Connect Load Shedding Devices To Prevent Generator Overload
12. 12 Volt Automotive Grade **Interstate** Battery
13. **Manufacturer required Break In-Service, and Oil Change for Generator**
14. **Two** Years Manufactures Limited Warranty
15. **Free Mobile Link Remote Monitoring**

Total Cost: \$25,000.00 Including Sales Tax

This Total Proposal Includes Parts & Labor As A Lump Sum. This Allows Us To Sell All Items Without Sales Tax. We Purchase All Items With Sales Tax Paid In Advance.

Payment **10%** down, **65%** at Delivery of Generator, Balance upon completion

MARK COSTIS

FIELD ENGINEER 727-365-1498

Acceptance of Proposal- The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above. Failure to make payments in accordance will result in additional cost for attorney fees.

X _____

Generac Generator

X _____ Date: 6/12/14

Print Johan Jongsma